



फक्ताडलुङ गाउँपालिका गाउँपालिकाको कार्यालय



फक्ताडलुङ गाउँपालिका
कार्यालय, ताप्लेजुङ
लाम्खोक, ताप्लेजुङ
न. प्रदेश, नेपाल

प. सं. ०७७।०७८

च. नं.: १६३

श्री सम्बन्धित सबैमा,

मिति: २०७७।०६।२६

- | | | |
|------------------------------------|---------------------------------|------------------------------------|
| १. नविन निर्माण सेवा | २. तमोरखोला निर्माण सेवा | ३. दोखु कन्स्ट्रक्सन |
| ४. डि.एम. कन्स्ट्रक्सन | ५. कान्छा लावति कन्स्ट्रक्सन | ६. कार्की कन्स्ट्रक्सन |
| ७. इवा कावेलि कन्स्ट्रक्सन | ८. एभेड कन्स्ट्रक्सन | ९. डि.बि. कन्स्ट्रक्सन |
| १०. नेचाली राई कान्छा कन्स्ट्रक्सन | ११. कञ्चनजंघा निर्माण सेवा | १२. जोङलुङ निर्माण सेवा |
| १३. नेशनल निर्माण सेवा | १४. पतडवा कन्स्ट्रक्सन प्रा.लि. | १५. पाथीभरा सर्भीस सेन्टर प्रा.लि. |

विषय: दरभाउपत्र आव्हान सम्बन्धमा।

प्रस्तुत सम्बन्धमा यस फक्ताडलुङ गाउँपालिकाको विभिन्न स्थानमा रहेका तपशिल बमोजिमका सडक मर्मत योजनाहरु सार्वजनिक खरिद ऐन, २०६३ को दफा ४१ को उपदफा (१) बमोजिम सोझै सिलबन्दी दरभाउपत्र मार्फत निर्माण गर्नुपर्ने भएकोले यस कार्यालयमा इच्छुक निर्माण कम्पनीहरुले ७ दिन भित्र तल उल्लेखित कार्यको लागि यसै पत्र साथ संलग्न **BOQ** मा आफ्नो दरभाउ भरी मिति २०७७।०७।०२ गते कार्यालय समय भित्र पेश गर्नुहुन सुचित गरिन्छ।

तपशिल

क्र.स.	योजनाको नाम	योजना रहने स्थान	ठेक्का नं.	कैफियत
१	इखाबु-सुडसाबु सडक मर्मत	फक्ताडलुङ-४	FRMTPJ/RRMP-DP/2077/78-01	
२	विपुधाप-साम्देन सडक मर्मत	फक्ताडलुङ-४	FRMTPJ/RRMP-DP/2077/78-02	
३	साँघु-विपुधाप सडक मर्मत	फक्ताडलुङ-४	FRMTPJ/RRMP-DP/2077/78-03	
४	साँघु-भाडबारी सडक मर्मत	फक्ताडलुङ-६	FRMTPJ/RRMP-DP/2077/78-04	
५	इजुङ पाँचथला -वडा कार्यालय सम्मको बाटो मर्मत	फक्ताडलुङ-३	FRMTPJ/RRMP-DP/2077/78-05	
६	ओडनेम्बा कृषि सडक मर्मत	फक्ताडलुङ-३	FRMTPJ/RRMP-DP/2077/78-06	
७	रविकला देखि दोकाने सम्म सडक मर्मत	फक्ताडलुङ-१	FRMTPJ/RRMP-DP/2077/78-07	
८	सविक-७ तिङदु देखि जोरखोला सम्म सडक मर्मत	फक्ताडलुङ-२	FRMTPJ/RRMP-DP/2077/78-08	
९	सिंवा देखि गुम्बा सम्म सडक मर्मत	फक्ताडलुङ-२	FRMTPJ/RRMP-DP/2077/78-09	
१०	खाम्थाक कृषि सडक मर्मत	फक्ताडलुङ-५	FRMTPJ/RRMP-DP/2077/78-10	

नोट: दरभाउ पत्र
साथ **BOQ** पेश गर्दा खासबन्दी
पेश गर्नुहुन

प्रमुख प्रशासकीय अधिकृत
२०७७।०६।२६



Phaktanglung Rural Municipality

Taplejung, Taplejung

Bill of Quantity

F/Y:-2077/78

योजनाको नाम: इखाबु-मुडसाबु सडक मर्मत

स्थान: फक्ताङलुङ ४, इखाबु

मु.अ.कर बाहेक जम्मा लागत:

Contract ID No. FRMTPJ/RRMP-DP/2077/78-01

330741.70

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount	Remarks
1	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	14000.00	m2				
2	Clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	1382.50	m3				
3	Earthwork Excavation in drain.	1	43.20	m3				
4	Stone solling work for roadway surface	1	14.00	m3				
5	Earth work excavation by Excavator (Class II , Bucket factor (Averaget excavating : 1, Job efficiency average :0.75 ,Standard Production for PC 150 : 71 m3per hour) - Average excavating (All types of Rock and Soil)	1	672	m3				
	Sub-Total							
	Vat @ 13 %							
	Grand Total							

Prepared By:

Arjun Kumar Yadav

Checked By:

Mr. Arjun Sigdel

Recd.No: 19600 "Civil"

Approved By:

Mr. Arjun Sigdel



Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: विपुधाप-साम्देन सडक मर्मत

F/Y:-2077/78

स्थान: फक्ताङलुङ ४, इखाबु

स.अ.कर बाहेक जम्मा लागत:

213759.034

Contract ID No. FRMTPJ/RRMP-DP/2077/78-02

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry, watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	7000.00	m ²			
2	Clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	922.25	m ³			
3	Earth work excavation by Excavator (Class II, Bucket factor (Averaget excavating : 1, Job efficiency average :0.75 ,Standard Production for PC 150 : 71 m ³ per hour) - Average excavating (All types of Rock and Soil)	1	1063.38	m ³			
	Sub-Total						
	Vat @ 13 %						
	Grand Total						

आ.प.न.नियन्त्रक
आ.प.न.नियन्त्रक

Prepared By:

Checked By:

Approved By:

Nec.Reg.No: 19600 "Civil"
Nec.Reg.No: 19600 "Civil"



Phaktianglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: साँघु-विपुथाप सडक मर्मत
स्थान: फक्ताङलुङ ४, इखाबु

F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:

281459.33

Contract ID No. FRMTPJ/RRMP-DP/2077/78-03

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation by surface Treatment of formation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	4375.00	m2			
2	Clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	1470.00	m3			
4	Earth work excavation by Excavator (Class II , Bucket factor (Averaget excavating : 1, Job efficiency average : 0.75 ,Standard Production for PC 150 : 71 m3per hour) - Average excavating (All types of Rock and Soil)	1	1711.50	m3			
Sub-Total							
Vat @ 13 %							
Grand Total							

Arjun Sigdel
नियन्त्रक

pared By:

Checked By:

Er. Arjun Sigdel
"Civil"

REC

No: 19600

"Civil"

Approved By:



योजनाको नाम: साघु भाङ्गारि सडक मर्मत

स्थान: फक्ताङलुङ ६ लेलेप

F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:

194741.89

Contract ID No. FRMTPJ/RRMP-DP/2077/78-04

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (in words)	Amount
1	Earth work excavation by Excavator (Class II , Bucket factor (Averaget excavating : 1, Job efficiency average :0.75 ,Standard Production for PC 150 : 71 m3per hour) - Average excavating (All types of Rock and Soil)	1	421.00	m3			
2	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	8000	m2			
3	clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley sides	1	1272	m3			
	Total Cost (कुल लागत)						
	Vat @ 13%						
	Total Cost (कुल लागत)						

Prepared By:-

Bidur Mahat
Ast. Sub-Engineer

Checked By:-
Er. Prabin Sigdel
Reg.No: 19600 "Civil"

Approved By:-

Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

ने नामः झुङ-पाँचथला वाडाकार्यलयसम्मको सडक मर्मत
सडाडलुङ ३, लिङखिम
बाहेक जम्मा लागतः

F/Y:-2077/78

440564.88

Contract ID No. FRMTPJ/RRMP-DP/2077/78-05

Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount	Remarks
earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry, watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	5400.00	m2				
earth work excavation by Excavator (Class II, Bucket capacity (Averaget excavating : 1, Job efficiency average 75 ,Standard Production for PC 150 : 71 m3per hour) - average excavating (All types of Rock and Soil)	1	653.13	m3				
stone salling work for roadway surface	1	83.20	m3				
Sub-Total							
Vat @ 13 %							
Grand Total							

Bidur Mahat
Sub-Engineer

Checked By: 
Recd. Reg. No.: 19600 "Civil"
Bidur Mahat
Sub-Engineer

Approved By:



Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: ओडनेम्बा कृषि सडक मर्मत
स्थान: फक्ताङलुङ-३, लिङखिम


F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:


201024.78


Contract ID No. FRMTPJ/RRMP-DP/2077/78-06

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	6391.60	m2			
2	Roadway excavation in all types of soil/rock including haulage and disposal all complete as directed by site incharge for	1	48.60	m3			
3	Stone solling work for roadway surface	1	35.00	m3			
Sub-Total							
Vat @ 13 %							
Grand Total							

Prepared By: 

Bidur Mahat
Ast. Sub-Engineer

Checked By: 
No: 19600 "Civil"

Approved By: 



Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: रबिकलादेखी दोकानेसम्म सडक मर्मत
स्थान: फक्ताङलुङ १, सावादिन

F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:

394528.48

Contract ID No. FRMTPJ/RRMP-DP/2077/78-07

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	7955.00	m2			
2	Clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	409.59	m3			
3	Stone solling work for roadway surface	1	74.00	m3			
	Sub-Total						
	Vat @ 13 %						
	Grand Total						

Bidur Mahat
Ast.Sub-Engineer

मर्मत
मर्मत

Er. Arjun Sigdel
Nec.Reg.No: 19600 "Civil"



Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: साविक-७ तिङ्दु देखि जोरखोला सम्म सडक मर्मत
स्थान: फक्ताङलुङ-१, खेजिनिम

F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:

176936.09

Contract ID No. FRMTPJ/RRMP-DP/2077/78-08

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry, watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	4550.00	m2			
2	Clearence of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	2150.75	m3			
	Sub-Total						
	Vat @ 13 %						
	Grand Total						

[Signature]

Er. Arjun Sigdel
Proc.Reg.No:19600 "Civil"

Arjun Kumar Yadav
जम्मा गर्ने
खेजिनिम



Phaktanglung Rural Municipality
Tapethok, Taplejung
Bill of Quantity

योजनाको नाम: सिंवा देखि गुम्बा सम्म बाटो मर्मत
स्थान: फक्ताङलुङ २, खेजिनिम

F/Y:-2077/78

मु.अ.कर बाहेक जम्मा लागत:

354319.89

Contract ID No. FRMTPJ/RRMP-DP/2077/78-09

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In word)	Amount
1	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	14000.00	m2			
2	Clearence of landslides in soil and ordinary rock by machine and disposal of the same on the valley side	1	3698.00	m3			
	Sub-Total						
	Vat @ 13 %						
	Grand Total						

आचार्य यादव
खेजिनिम

pared By:

Checked By: Mr. Arjun Sigdel
Reg. No: 19600 "Civil"

Approved By: [Signature]
Reg. No: 19600 "Civil"

योजनाको नाम: खाश्चाक सडक मर्मत
स्थान: फक्ताङलुङ ५ तापेथोक

मु.अ.कर बाहेक जम्मा लागत:

55905.25

Contract ID No. FRMTPJ/RRMP-DP/2077/78-10

F/N:-2077/78



Phaktanglung Rural Municipality

Taplejung

Bill of Quantity

S.N.	Description of works	No.	Quantity	Unit	Rate	Rate (In Words)	Amount	Remarks
1	Earth work excavation by Excavator (Class II, Bucket factor (Averaget excavating : 1, Job efficiency average :0.75, Standard Production for PC 150 : 71 m3per hour) - Average excavating (All types of Rock and Soil)	1	246.50	m3				
2	Earth work Preparation and surface Treatment of formation Preparation and surface Treatment of formation by removing mud and slurry , watering to the extent needed to maintain desired moisture content compaction all complete as per drawing and technical specifications	1	1750.00	m2				
3	clearance of landslides in soil and ordinary rock by machine and disposal of the same on the valley sides	1	275.25	m ³				
	Sub-Total							
	Vat@13%							
	Grand Total							

Prepared By:-
.....

Bidur Mahat
Ast. Sub-Engineer

Checked By:-
.....

Er. Arjun Sigdel
Nec.Reg.No: 19600 "Civil"

Approved By:-
.....

प्रमुख प्रशासकाय अधिकारी